

Phone : +91-1477-220098, 220087
Fax : +91-1477-220027, 220049
E-mail : jkc.nbh@jkcement.com
Web : www.jkcement.com

J.K. Cement Works, Mangrol C/o. Kailash Nagar-312617, Nimbahera Distt. Chittorgarh (Raj.) INDIA

CIN: L17229UP1994PLC017199

ISO 9001:2008, ISO 14001:2004 & OHSAS 18001: 2007 CERTIFIED COMPANY

Ref. No.: MGR-PC -13/ 2-392

27.09.2018

To,

The Member Secretary

Rajasthan State Pollution Control Board

4, Industrial Area
Jhalana Doongri

JAIPUR - 302004 (Raj)

SUBJECT: Environmental Statement for the year 2017-2018 (02 Copies)

Dear Sir,

Kindly find herewith enclosed **Environment Statement Report** of **Tilakhera Limestone Mine** for the **year 2017-2018** for your reference and record. We trust you will find the same in order.

Thanking You.

Yours Faithfully For J.K. Cement Works, Mangrol

S.K. Acharya Astt. V.P. (E & I)

Encl.:a/a

Copy to -

The Regional Officer, Rajasthan State Pollution Control Board, Near FCI Godown, Chanderia, Distt.- CHITTORGARH (RAJ)

Corporate & Registered Office : Kamla Tower, Kanpur-208001, (U. P.) INDIA Phone : +91-512-2371478 to 81 Fax : 2399854 E-mail : ho.grey@jkcement.com



- J. K. Cement Works, Nimbahera
- J. K. Cement Works Mangrol
- J. K. Cement Works, Gotan
- J. K. Cement Works, Jharli
- J. K. Power, Bamania
- J. K. Cement Works, Muddapur
- J. K. White Cement Works, Gotan
- J. K. White, Katni





Government of India Ministry of Environment and Forest "FORM – V"

(See rule 14)

ENVIRONMENTAL STATEMENT FOR THE FINANCIAL YEAR ENDING THE $31^{\rm ST}$ MARCH 2018

Mangrol-Tilakhera Mine of M/s J.K. Cement works, MANGROL (Raj.)

PART - A

(I)	Name & Address of the Owner / Occupier of the Industry Operation or Process	S.K. Rathore Unit Head J.K. Cement Works, MANGROL Kailash Nagar: 312 617 NIMBAHERA, Chittorgarh (Raj.)
(II)	Industry Category Primary (STC CODE) Secondary (SIC CODE)	Polluting (Non – Hazardous) PRIMARY STC Category
(III)	Production Capacity	1.6 MMTPA
(IV)	Year of Establishment	Year 1979
(V)	Date of last Environmental Statement Submitted	16 th September, 2017

PART - B

Water & Raw Material Consumption

A. Water

(i)	Over All Consumption	-	KLD
	Process	-	47.0 (Spray on Road / Mining, Drilling etc.)
	Cooling:		Nil
	Domestic		3.0
	Total	-	50.0

Consumption per unit of production (ii)

Name of the Product		sumption per unit of t Output
	During the Previous Financial Year	During the Current Financial Year
Limestone	10.73 Ltrs / Unit	12.16 Ltrs / Unit

B. Raw Material Consumption

9 9

Name of the Raw Material		Name of Product	Consumption of Raw Mater Product Output	ial per Unit
	6 g 9		During the Previous Financial Year	During the Current Financial Year
HSD		Limestone	0.484 Ltrs. Per Ton	0.578 Ltrs. Per Ton

PART - C Pollutant Discharge To Environment / Unit of Output

(Parameters as specified in the consent issued)

(1)	Pollutants	Quantity of Pollutants Discharged (Mass / day)	Concentrations of Pollutants in discharged (Mass / volume)	Percentage of variation from prescribed standard with reasons
(a)	Water			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
(i)	Colonial	NIL		1. 1980.
(ii)	Industrial	NIL		

WATER ANALYSES RESULTS

SAMPLE	MINE PITWATER	HANDPUMP NEAR	TUBEWELL WATER
PARTICULAR	(Dated 03.11.2017)	SHAHBAD	(Dated 23.11.2017)
		(Dated 03.11.2017)	
COLOUR & ODOUR	Clear & Natural	Clear & Natural	Clear & Natural
Ph	7.62	7.18	7.92
TSS	18	22	4
TOTAL HARDNESS	200	508	288
Ca+ HARDNESS	124	456	102.4
Mg+ HARDNESS	76	52	7.68
CONDUTIVITY	445	1230	773.2
TDS	267	738	472
CHLORIDES *	28	147	38
TURBIDITY	1.24	2.46	0.18

^{*}All the parameters are expressed in mg/ltr except PH & Turbidity

J.K. CEMENT WORKS, MANGROL

Tilakhera MINE

AMBIENT AIR QUALITY MONITORING DATA FOR SPM

(Monthly Average In MICROGRAMS/CUBIC METER)

Year 2017-18

Month	NEAR MINE OFFICE	NEAR RAWANA OFFICE	
April-17	344.0	376.0	
May-17	327.0	387.0	
June-17	311.0	364.0	
July-17	276.0	329.0	
August-17	303.0	340.0	
September-17	317.0	368.0	
October-17	329.0	381.0	
November-17	335.0	372.0	
December-17	347.0	384.0	
January-18	327.0	369.0	
February-18	343.0	384.0	
March-18	322.0	375.0	

PART - D

(As specified under Hazardous Waste & Other waste Management rules-2016)

Hazardous Waste		Total Qua	ntity (Kgs.)
		During the Previous Financial Year	During the Current Financial Year
(a)	From Process	Nil.	Nil.
b)	From Pollution Control Facilities.	N.A.	N.A.

PART - E

SOLID WASTES

	Total Qu	uantity
	During the Previous Financial Year	During the Current Financial Year
n) From Process	N.A.	N.A.
) From Pollution Control facilities	N.A.	N.A.
) (i) Qty. recycled or reused with in the unit.	NIL	NIL
(ii) Sold	NIL	NIL
(iii) Disposed	NIL	NIL

PART-F

PLEASE SPECIFY THE CHARACTERISATIONS (IN TERMS OF COMPOSITION AND QUANTUM) OF HAZARDOUS AS WELL AS SOLID WASTES AND INDICATES DISPOSAL PRACTICE ADOPTED FOR BOTH THESE CATEGORIES OF WASTES.

There is no hazardous as well as Solid Waste produced.

PART - G

IMPACT OF THE POLLUTION ABATEMENT MEASURES TAKEN ON CONSERVATION OF NATURAL RESOURCES AND ON THE COST OF PRODUCTION.

AIR

J

J

3

9

9

Mining operation and related activities are designated as potential sources as under:

- Emissions from Diesel operated earth moving machinery e.g. Sulphur Dioxide (SO₂), Oxides
 of Nitrogen (NO_x), Suspended Particulate Matter (SPM), Respirable Particulate Matter
 (RPM) etc.
- Local air borne dust due to excavation, drilling and blasting operations.
- Air borne dust pollution due to loading, unloading, transportation etc.

From the base line study the Air Quality near on going mining activities, the pollutants level was observed very low or below the detection limit except SPM and RPM.

There is no impact observed on vegetation & water bodies in the surrounding areas, as it will be suppressed at its generating sources.

The following measures are taken to suppress the dust at the source as well as to prevent the same, spreading in the atmosphere:

- Wet drilling system is provided on all drill machines.
- Regular water sprinkling on haul road during operation.
- Optimize blasting parameters for proper fragmentation to reduce dust generation.
- Plantation and development of Green Belt along the Haul Roads and Working Pits.

WATER

Being Mechanised Limestone mine, it requires water mainly for Wet Drilling, Road Spraying, Green Belt Development, and Machineries Washing. Water consumption is around 50 KLD. The source of water is the accumulated rainwater in the lower most benches. There is no liquid effluent / waste water.

NOISE

Noise is generated in the mine due to following mining activities:

- Excavation, drilling, blasting and operations of HEMM.
- Transportation and handling of material.

The results of base line noise level survey are well below the permissible limit except near machinery while operating. The noise generating sources are scattered within the whole mining area. All the sources will not generate the noise simultaneously hence; the noise level would not alter the noise environment significantly. The noise level reduces with increase in distance from the source.

The following measures are taken to reduce the noise level at the source as well as to prevent the same, spreading in the atmosphere:

- 1. Providing enclosures for noise sources to reduce dispersion of noise like cabin in HEMM.
- 2. Proper maintenance and lubrication of machinery rotating parts.

- 3. Use of non electric delay detonator (Nonel) on surface in place of detonating fuse.
- 4. Use of low quantity detonating fuse (8gm/m in place of 10gm/m).
- 5. By covering the detonating fuse as well as detonators under drill cutting or the fine material.
- 6. By providing earmuffs and earplugs to eligible miners.
- 7. Blasting between 12.00 noon to 3.00 PM when air density is low.
- 8. Use of Air Decking & sufficient column stemming in the blast holes.
- 9. Use of NONEL.

J.K. CEMENT WORKS, MANGROL

<u>Tilakhera MINE</u>

NOISE LEVEL MONITORING DATA

Monthly Average In dB (A)

Year: 2017-18

Month	NEAR N	MINE OFFICE	NEAR RAV	NEAR RAWANA OFFICE	
World	Day Time	Night Time	Day Time	Night Time	
April-17	67.8	58.3	68.9	60.2	
May-17	68.4	59.2	70.0	61.0	
June-17	69.6	60.3	71.5	58.9	
July-17	68.6	61.2	69.8	59.3	
August-17	67.3	59.8	68.8	60.5	
September-17	68.2	60.0	70.5	62.7	
October-17	70.1	61.5	71.2	62.4	
November-17	68.3	60.5	72.6	61.5	
December-17	66.8	58.2	69.3	60.5	
January-18	70.5	61.9	72.1	62.1	
February-18	67.5	59.3	69.6	61.2	
March-18	69.9	60.1	70.4	60.8	

GROUND VIBRATION

M/s IDL and CIMFR (CSIR) had carried out vibration study & recommended safe charge per delay at various distances for keeping the parameters of blasting well within the limit.

The following steps are taken to control ground vibration:

- 1. Optimize drilling parameters like spacing, burden and sub-grade drilling.
- 2. Optimize maximum charge per delay.
- 3. Use of Non Electric Detonator with delay-blasting technique.
- 4. Monitoring of ground vibration by "Mini-mate".

PART - H

ADDITIONAL MEASURES / INVESTMENT PROPOSALS FOR ENVIRONMENTAL PROTECTION INCLUDING ABATEMENT POLLUTION, PREVENTION OF POLLUTION.

EXPENDITURE INCURRED ON ENVIRONMENTAL PROTECTION MEASURES DURING YEAR 2017-2018

S. No.	Activity	Recurring Cost per Annum (Rs.)
1.	Pollution control expenses (Others)	73260
2.	Pollution control expenses (Statutory)	265958
3.	Gardening Expenses	502430
4.	CSR Expenses	1459493
	Total (Rs.)	2301141/-

PART - I

ANY OTHER PARTICULARS FOR IMPROVING THE QUALITY OF ENVIRONMENT.

Mine has planted 2030 plants in and around mining area during the period under review.

Dist. CHITTORGARH (Rail)

For JK CEMENT WORKS, MANGROL